



KERALA AGRICULTURAL UNIVERSITY

*Directorate of Physical Plant,
KAU. P O, Vellanikkara, Thrissur-680656.
Ph: 0487 2438155, e-Mail: dpp@kau.in*

A7/1037/17

14/03/2018

Re-Quotation Notice No:26/2017-18

Sealed competitive quotations are invited from the Manufactures / Dealers / Contractors on or before **3 pm** on **26/03/2018** for 140kVA and 82.5kVA Diesel Generator sets (one each) with following specifications.

1) Details for 140kVA DG Set for CCBM College, KAU Main Campus, Vellanikkara.

PART - A - Supply and Installation of DG Set (140kVA)

Supply, installation, testing and commissioning of 140 kVA, 415V, 50Hz, 0.8 pf Diesel Generator set with integral acoustic enclosure as per CPCB norms with standard accessories including self starting arrangements, standard control panel etc. complete.

Preferable Make -

Engine: - Kirlosker / Cummins /Greaves /Volvo Eicher

Alternator: - Kirlosker / Stamford / Greaves / KEL

PART-B - Allied Electrical works (Schedule Attached separately-Part-1B)

PART-C - Obtaining approval from Electrical Inspectorate and allied bodies.

Preparation of schematic diagrams and other drawings for obtaining approval from Electrical Inspectorate including inspection fee etc. (on production of actual documents of fee remitted)

2) Details for 82.5kVA DG Set for Central Library, KAU Main Campus, Vellanikkara.

PART - A - Supply and Installation of DG Set (82.5kVA)

Supply, installation, testing and commissioning of 82.5 kVA, 415V, 50Hz, 0.8 pf Diesel Generator set with integral acoustic enclosure as per CPCB norms with

standard accessories including self starting arrangements, standard control panel etc. complete.

Preferable Make –

Engine: - Kirlosker / Cummins /Greaves /Volvo Eicher

Alternator: - Kirlosker / Stamford / Greaves / KEL

PART –B – Allied Electrical works (Schedule Attached separately- Part-2B)

PART – C – Obtaining approval from Electrical Inspectorate and allied bodies.

Preparation of schematic diagrams and other drawings for obtaining approval from Electrical Inspectorate including inspection fee etc. (on production of actual documents of fee remitted)

Terms and conditions:

1. The rate should be including all taxes, levies, duties, loading, transportation, unloading, installation, testing, commissioning and allied charges.
2. Two year comprehensive warranty should be given for the supplied items and warranty certificates furnished with the supply of items.
3. Period of Supply is within 30 days after confirming order.
4. 75% of the machine cost will be paid as advance to the supplier after the delivery of the DG set forwarded through the AE/AEE concerned and balance 25% will be paid after commissioning and sanction / approval from Electrical Inspectorate.

Additional details if any required and other terms and conditions can be had from the office of the undersigned.

Sd/-
Director of Physical Plant