

KERALA AGRICULTURAL UNIVERSITY
Directorate of Physical Plant
QUOTATION SCHEDULE

Part-1B

Name of work:- KAU - CCBM, Installation of Generated supported UPS. - Allied electrical woks for the installation of DG Set.

| Item No. | Quantity | Description | Rate | Per Unit | (Rate in words) | Amount |
|----------|----------|---|-------|----------|--|--------|
| 1 | 1 No | Supply and installation of 315A, 4pole on load change over switch in suitable sheet steel enclosure including connection | 18183 | /Each | (Rs Eighteen thousand one hundred and eighty three only) | 18183 |
| 2 | 1 No | Supply and fixing 315A, 4pole switch disconnecter fuse unit in sheet steel enclosure with HRC fuse links using suitable fixing arrangements including connection | 16498 | /Each | (Rs Sixteen thousand four hundred and ninety eight only) | 16498 |
| 3 | | Supplying and drawing 1.1 KV grade PVC insulated and sheathed armoured aluminium power cable as per directions of the Deptl. Officers. Clamping on wall / ceiling / truss etc. using conduit saddles / metal clamps etc. | | | | |
| 4 | 30 m | 3.5x185sq.mm size | 1076 | /m | (Rs One thousand and seventy six only) | 32280 |
| | 2 Nos. | 3.5x185sq.mm size | 825 | /Each | (Rs Eight hundred and twenty fiveonly) | 1650 |

| Item No. | Quantity | Description | Rate | Per Unit | (Rate in words) | Amount |
|----------|----------------------|---|-------|---------------------|--|--------|
| 5 | 4 Nos | Supply and providing plate earthing using 600X600X6.3 mm CI/GI earth plate with required length of 20 mm GI watering pipe with funnel including fixing arrangements, filling charcoal and salt around earth plate, providing man hole with CI cover etc. including civil works complete as per directions of the Deptl. officers. | | | (Rs Four thousand seven hundred and eighty three only) | 19132 |
| | | | 4783 | /Each | | |
| 6 | | Providing GI pipe as protective cover to the earth lead. | | | | |
| a | 10 m | 32 mm or nearest size. | 215 | /m | (Rs Two hundred and fifteen only) | 2150 |
| b | 10 m | 40 mm or nearest size. | 240 | /m | (Rs Two hundred and forty only) | 2400 |
| c | 10 m | 50 mm or nearest size. | 307 | /m | (Rs Three hundred and seven only) | 3070 |
| 7 | | Providing Copper strip for earth connection | | | | |
| | 50 m | 25X3 mm size | 544 | /m | (Rs Five hundred and forty four only) | 27200 |
| 8 | | Supplying and drawing bare copper earth conductor along with wiring / cable / through pipes etc as required. | | | | |
| a | 60 m | No.08 SWG (4.06 mm) | 85 | /m | (Rs Eighty five only) | 5100 |
| b | 10 m | No.04 SWG (5.89 mm) | 164 | /m | (Rs One hundred and sixty four only) | 1640 |
| 9 | 5 m ³ | Earth work excavation in all classes of soil and depositing with lead upto 50 M and lift upon 1.50 M including neat banking and back filling etc. complete. | 1259 | /10m ³ | (Rs One thousand two hundred and fifty nine only) | 630 |
| 10 | 2.00 m ³ | Cement concrete 1:3:6 using 20mm broken stone. | 54.50 | /10 dm ³ | (Rs Fifty four and Ps. Fifty only) | 10900 |
| 11 | 1750 dm ³ | Cement concrete 1:2:4 using 20mm broken stones including watering, curing etc., complete | 75.50 | /10dm ³ | (Rs Seventy five and Ps fifty only) | 13213 |
| 12 | 10.00 m ² | Plastering with CM 1:4,12mm thick | 1637 | /10 m ² | (Rs. One thousand six hundred and thirty seven only) | 16370 |

| Item No. | Quantity | Description | Rate | Per Unit | (Rate in words) | Amount | |
|-------------|------------------|---|--------|-----------------|---|--------------------------------------|---------------|
| 13 | 2 m ² | Supply and providing chequered type SMC sheet - 6mm thick. | 7636 | /m ² | (Rs Seven thousand six hundred and thirty six only) | 15272 | |
| 14 | 1 Nos | Supply and fixing Dry chemical powder type fire exhinguisher 5kg in position | 2404 | /Each | (Rs Two thousand four hundred and four only) | 2404 | |
| 15 | 1 Nos | Supply and fixing First aid chart duly framed and placed in position | 242 | /Each | (Rs Two hundred and fourty two only) | 242 | |
| 16 | 1 Nos. | Supply of LT Cable route marker cast iron spike and inscription and fixing in CC as required. | 297 | /Each | (Rs. Two hundred and ninety seven only) | 297 | |
| Market Rate | | | | | Quotation PAC | 188631 | |
| 15 | 1 | No | 207.00 | 207 | Market Rate | 207 | |
| | | | | | | Quotation PAC less cost of MR | 188424 |

(Rupees One lakh eight eight thousand four hundred and twenty four only)

I / We..... contractor do hereby agreed to undertake to execute the work at% above / below estimate rate, less cost of market rate.

Contractor

Director of Physical Plant