



KERALA AGRICULTURAL UNIVERSITY

Directorate of Physical Plant,
KAU. P O, Vellanikkara, Thrissur-680656.
Ph: 0487 2438155, e-Mail: dpp@kau.in

A7/1037/17

31/01/2018

Re-Quotation Notice No: 21/2017-18

Sealed competitive quotations are invited from the Manufacturers / Dealers / Contractors on or before **3 pm** on **09/02/2018** for 140kVA and 82.5kVA Diesel Generator sets (one each) with following specifications.

1) Details for 140kVA DG Set for CCBM College, KAU Main Campus, Vellanikkara.

Supply, installation, testing and commissioning of 140 kVA, 3 phase Diesel Generator set with integral acoustic enclosure as per CPCB norms with standard accessories including self starting arrangements, standard control panel etc. complete. Allied electrical connections like plate earthing (Minimum 4nos.), SFU of capacity 315A 4pole, on load change over switch of capacity 315A, 4pole, cabling (3.5x185sq.mm 30mtrs Aprox.), concrete trench for cable laying, concrete foundations, fire extinguisher, rubber mat, first aid chart etc. as per standard norms of statutory bodies and directions of KAU departmental officers, preparation of schemes and obtaining approval/sanction from the Electrical Inspectorate.

2) Details for 82.5kVA DG Set for Central Library, KAU Main Campus, Vellanikkara.

Supply, installation, testing and commissioning of 82.5 kVA, 3 phase Diesel Generator set with integral acoustic enclosure as per CPCB norms with standard accessories including self starting arrangements, standard

control panel etc. complete. Allied electrical connections like plate earthing (Minimum 3nos.), on load change over switch of capacity 160A, 4pole, cabling (3.5x95sq.mm 20mtrs Aprox.), concrete trench for cable laying, concrete foundations, fire extinguisher, rubber mat, first aid chart etc. as per standard norms of statutory bodies and directions of KAU departmental officers, preparation of schemes and obtaining approval/sanction from the Electrical Inspectorate.

Preferable Make –

Engine: - Kirlosker / Cummins /Greaves

Alternator: - Kirlosker / Stamford / Greaves

Terms and conditions:

1. The rate should be including all taxes, levies, duties, loading, transportation, unloading, installation, testing, commissioning and allied charges.
2. Two year comprehensive warranty should be given for the supplied items and warranty certificates furnished with the supply of items.
3. Period of Supply is within 30 days after confirming order.
4. 75% of the machine cost will be paid as advance to the supplier after the delivery of the DG set forwarded through the AE/AEE concerned and balance 25% will be paid after commissioning and sanction / approval from Electrical Inspectorate.

Additional details if any required and other terms and conditions can be had from the office of the undersigned.

Sd/-
Director of Physical Plant