KERALA AGRICULTURAL UNIVERSITY

Name of work : RKVY Project-Strengthening of Pesticide Residue lab-Construction of a Car porch at College of Agriculture,Vellayani

S C H E D U L E

Sl.No	Quantity		Description of items	Unit	Rate in figures	Rate in words	Amount
1	18.00	m	Supplying and fixing 90 mm or nearest dia GI pipes including cost of closing the ends with necessary plates etc. for vertical posts	m	656.00	(Rupees Six Hundred and Fifty Six Only)	11808.00
2	0.50	m3	Cement concrete 1:2:4 using 20 mm broken stone including all form work, watering, curing etc. complete for hold fast blocks	10dm3	115.00	(Rupees One Hundred and Fifteen Only)	5750.00
3	3.00	Qtl	Steel work welded in built up sections, trusses,ridges,rafters, wall plates and framed work with approved quality square/ rectangular Galvanised Pipes etc.cutting,fabricating and hoisting including applying a coat of Zinc rich primer and closing the free ends with plates of required size etc complete.	Qtl	11307.00	(Rupees Eleven Thousand Three Hundred and Seven Only)	33921.00
4	80.00	m2	Roofing with Poly carbonate corrugated sheet 0.8 mm thick with over laps 150mm at ends and GI hooks or crank bolts and nuts including plain washers and bitumen washers etc. complete.	10m2	22821.00	(Rupees Twenty Two Thousand Eight Hundred and Twenty One Only)	182568.00
5	80.00	m2	Painting with synthetic enamel paint using approved quality as specified two coats for new iron work after cleaning the surface.	10m2	784.00	(Rupees Seven Hundred and Eighty Four Only)	6272.00
6	5.00	m2	Plastering with CM 1:4 12mm thick one coat floated and trowelled smooth with neat cement flushing coat.	10m2	2526.00	(Rupees Two Thousand Five Hundred and Twenty Six Only)	1263.00
			Tender PAC				**241582.00**
			Deduct				
			Market Rate				**35500.00**
			Less deduction				**206082.00**
			PAC less cost of market rate				**206082.00**

(Rupees Two Lakh Six Thousand and Eighty Two Only)

Contractor **Executive Engineer**