| Name of Work: Providing interlock and approach road in Poopoli ground at RARS Ambalavayal. | | | | | | |
|---|---|---|---|---|---|---|
| Sl. No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P |
| | | | | Figure | Words | |
| 1.00 | 2.8.1 : Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil | 10.00 | cum | 238.18 | Rupees two hundred and thirty eight and eighteen paisa only | 2381.80 |
| 2.00 | 4.1.3 : Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) | 18.00 | cum | 7846.86 | Rupees seven thousand eight hundred and fourty six and eighty six paisa only | 141243.48 |
| 3.00 | 5.9.1 : Centering and shuttering including strutting, etc. and removal of form for:Foundations, footings, bases of columns, etc for mass concrete | 140.00 | sqm | 277.62 | Rupees two hundred and seventy seven and sixty two paisa only | 38866.80 |
| 4.00 | 50.13.1 : 9 mm cement plastering of mix : 1:3 (1 cement : 3 fine sand ) including all cost of materials, labour charges etc complete9 mm cement plastering of mix : 1:3 (1 cement : 3 fine sand ) including all cost of materials, labour charges etc complete | 210.00 | sqm | 231.31 | Rupees two hundred and thirty one and thirty one paisa only | 48575.10 |

Signature of Tenderer with seal

| Name of Work: Providing interlock and approach road in Poopoli ground at RARS Ambalavayal. | | | | | | |
|---|---|---|---|---|---|---|
| Sl. No. | Description of work | No. or Qty. | Unit | Estimated Rate | | AMOUNT Rs. P |
| | | | | Figure | Words | |
| 5.00 | 13.46.1 : Finishing walls with Acrylic Smooth exterior paint of required shade:New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) | 210.00 | sqm | 137.49 | Rupees one hundred and thirty seven and ninety four paisa only | 28872.90 |
| 6.00 | 16.91.1 : Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.60mm thick cement concrete paver block of M-35 grade with approved colour, design& pattern. | 1120.00 | sqm | 1082.35 | Rupees one thousand and eighty two and thirty five paisa only | 1212232.00 |
| Total Estimated Cost in Figures | | | | | | 1472172.08 |
| Quoted Amount | | | | | | 1472172.00 |
| Quoted Rate in Words | | Rupees fourteen lakh seventy two thousand one hundred and seventy two only | | | | |

Signature of Tenderer with seal