Name of Work: Relaying concrete flooring for threshing yard at RARS ,Pattambi

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	od1121/2017_2018 : Coolie engaged for Chipping floor plaster	10.00	each	586.68	Rupees five hundred & eighty six and paise sixty eight only	5866.80
2.00	15.56 : Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	130.00	sqm	30.74	Rupees thirty and paise seventy four only	3996.20
3.00	15.7.4 : Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.In cement mortar	1.00	cum	1156.61	Rupees one thousand one hundred & fifty six and paise sixty one only	1156.61
4.00	13.1.1 : 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	135.00	sqm	237.37	Rupees two hundred & thirty seven and paise thirty seven only	32044.95
5.00	13.7.1 : 12 mm cement plaster finished with a floating coat of neat cement of mix:1:3 (1 cement : 3 fine sand)	795.00	sqm	311.28	Rupees three hundred & eleven and paise twenty eight only	247467.60
6.00	od1470/2017_2018 : White cement priming coat over newly plastered surface after cleaning the surface	130.00	sqm	15.92	Rupees fifteen and paise ninety two only	2069.60

Signature of Tenderer with seal

7.00	5.1.2 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size	1.00	cum	8530.57	Rupees eight thousand five hundred & thirty and paise fifty seven only	8530.57
8.00	5.1.3 : Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	64.50	cum	7922.96	Rupees seven thousand nine hundred & twenty two and paise ninety six only	511030.92
9.00	5.9.2 : Centering and shuttering including strutting, etc. and removal of form for:Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	40.00	sqm	519.63	Rupees five hundred & nineteen and paise sixty three only	20785.20
10.00	od1480/2017_2018 : Providing and fixing in position 6 mm thick and 80 mm deep multi wood , including cost of sealing compound in expansion joints.	290.00	per metre	61.09	Rupees sixty one and paise nine only	17716.10
11.00	od1122/2017_2018 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete Thermo - Mechanically Treated bars	1600.00	kilogram	77.68	Rupees seventy seven and paise sixty eight only	124288.00
12.00	15.28.2 : Dismantling roofing including ridges, hips, velleys and gutters etc., and stacking the material within 50 metres lead of :Asbestos Sheet	60.00	sqm	45.09	Rupees fourty five and paise nine only	2705.40

Signature of Tenderer with seal

13.00	50.12.3.1 : Providing departmental asbestos corrugated sheets roofing up to any pitch and fixing with polymer coated J,or L hooks, bolts and nuts 8 mm dia. G.I plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete (excluding the cost of purlins, rafters and trusses), including cutting sheets to size and shape wherever required.	30.00	sqm	107.88	Rupees one hundred & seven and paise eighty eight only	3236.40
14.00	providing asbetos corrugated/trafford sheets roofing up to any pitch and fixing with polymer coated J, or L hooks,bolts nad nuts 8 mm dia G.I plain and bitumen washers or with sel drilling fastener and EPDM washers etc.complete.(excluding the cost of purlins,rafters and trusses),including cutting sheets to size and shape wherever required.	30.00	sqm	348.29	Rupees three hundred & fourty eight and paise twenty eight only	10448.70
Total Estimated Cost in Figures						991343.05
Quoted Amount					991343	991343
Quoted Rate in Words		Rupees Nine laks ninety one thousand three hundred and fourty three only				

Signature of Tenderer with seal