Name of Work: Repair works in existing GL water tanks in block no-10 and 9 at PRS Panniyur.

PRINT

HELP

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		UT P
				Figure	Words	
1.00	15.56 : Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	110.00	sqm	27.50	Rupees Twenty Seven and Paise Fifty Only	3025.00
2.00	od153/2016_2017 : Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up tot floor five level excluding cost of centering, shuttering, finishing and reinforcement :(With 200 m Head Load)1:1.5:3(1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	10.50	cum	9995.66	Rupees Nine Thousand Nine Hundred & Ninety Five and Paise Sixty Six Only	104954.43
3.00	5.9.2 : Centering and shuttering including strutting, etc. and removal of form for:Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	60.00	sqm	494.80	Rupees Four Hundred & Ninety Four and Paise Eighty Only	29688.00
4.00	od406/2016_2017 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete above plinth level.Thermo - Mechanically Treated bars (With 200 m head load)	940.00	kg	93.64	Rupees Ninety Three and Paise Sixty Four Only	88021.60
5.00	50.18.9.7.1 : Providing and fixing PVC pipes includings of pipes with one step PVC solvent cement, trenching refilling & testing of joints complete as per direction of Engineer in Charge. 63 mm dia 6Kgf/cm2	15.00	metre	264.99	Rupees Two Hundred & Sixty Four and Paise Ninety Nine Only	3974.85
6.00	od458/2016_2017 : 12 mm cement plaster finished with a floating coat of neat cement of mix:1:3 (1 cement : 3 fine sand)(With 200 m head load)	110.00	sqm	298.00	Rupees Two Hundred & Ninety Eight Only	32780.00

Signature of Tenderer with seal

Name of Work: Repair works in existing GL water tanks in block no-10 and 9 at PRS Panniyur.

PRINT

HELP

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		JT P
				Figure	Words	
7.00	18.10.6 : Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work- Exposed on wall50 mm dia nominal bore	6.00	metre	723.00	Rupees Seven Hundred & Twenty Three Only	4338.00
8.00	14.54.1 : Painting with synthetic enamel paint of approved brand and manufacture of required colour to an give even shade:One or more coats on old work	30.00	sqm	66.51	Rupees Sixty Six and Paise Fifty One Only	1995.30
9.00	od155/2016_2017 : Supplying and fixing 50mm GM full way wheel valve (best quality ISI marked)	3.00	each	1800.35	Rupees One Thousand Eight Hundred and Paise Thirty Five Only	5401.05
10.00	od471/2016_2017 : Providing border 75mm wide and 15mm thick in CM (With 200 m head load)	31.00	metre	46.31	Rupees Fourty Six and Paise Thirty One Only	1435.61
11.00	od191/2016_2017 : Man mazdoor engaged for covering the tank steel and plastic sheet etc complete..	3.00	each	524.08	Rupees Five Hundred & Twenty Four and Paise Eight Only	1572.24
12.00	15.56 : Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	145.00	sqm	27.50	Rupees Twenty Seven and Paise Fifty Only	3987.50
13.00	od470/2016_2017 : Demolishing laterite work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.In cement mortar	1.00	cum	838.47	Rupees Eight Hundred & Thirty Eight and Paise Fourty Seven Only	838.47
14.00	od468/2016_2017 : Laterite masonary with neatly dressed stone of size 29x20x14 cm or nearest size in cement mortar 1:6 for foundation and basement including all cost of material, labour charges etc.	.80	cum	6255.29	Rupees Six Thousand Two Hundred & Fifty Five and Paise Twenty Nine Only	5004.23

Signature of Tenderer with seal

Name of Work: Repair works in existing GL water tanks in block no-10 and 9 at PRS Panniyur.

PRINT

HELP

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		UNIT P
				Figure	Words	
15.00	5.2.2 : Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up tot floor five level excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3(1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	8.50	cum	9701.70	Rupees Nine Thousand Seven Hundred & One and Paise Seventy Only	82464.45
16.00	5.9.2 : Centering and shuttering including strutting, etc. and removal of form for:Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	57.00	sqm	494.80	Rupees Four Hundred & Ninety Four and Paise Eighty Only	28203.60
17.00	5.22.6 : Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars	800.00	kilogram	93.39	Rupees Ninety Three and Paise Thirty Nine Only	74712.00
18.00	50.4.1.1 : Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) up to floor five level excluding the cost of centering, shuttering, finishing for leveling coarse of floor and roof etc.Providing and laying in position cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) up to floor five level excluding the cost of centering, shuttering, finishing for leveling coarse of floor and roof etc.	15.00	cum	7457.47	Rupees Seven Thousand Four Hundred & Fifty Seven and Paise Fourty Seven Only	111862.05
19.00	13.7.1 : 12 mm cement plaster finished with a floating coat of neat cement of mix:1:3 (1 cement : 3 fine sand)	90.00	sqm	297.80	Rupees Two Hundred & Ninety Seven and Paise Eighty Only	26802.00

Signature of Tenderer with seal

Name of Work: Repair works in existing GL water tanks in block no-10 and 9 at PRS Panniyur.

PRINT

HELP

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT
				Figure	Words	
20.00	13.7.2 : 12 mm cement plaster finished with a floating coat of neat cement of mix:1:4 (1 cement : 4 fine sand)	60.00	sqm	278.74	Rupees Two Hundred & Seventy Eight and Paise Seventy Four Only	16724.40
21.00	50.18.8.7.1 : Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge. Concealed work including cutting chases and making good the wall etc. 63 mm pipe 6 Kgf/cm2	8.00	metre	447.11	Rupees Four Hundred & Fourty Seven and Paise Eleven Only	3576.88
22.00	18.10.6 : Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. Internal work- Exposed on wall50 mm dia nominal bore	6.00	metre	723.00	Rupees Seven Hundred & Twenty Three Only	4338.00
23.00	od155/2016_2017 : Supplying and fixing 50mm GM full way wheel valve (best quality ISI marked)	3.00	each	1800.35	Rupees One Thousand Eight Hundred and Paise Thirty Five Only	5401.05
24.00	od469/2016_2017 : Man mazdoor engaged for clearing the primises of the tank	3.00	each	524.08	Rupees Five Hundred & Twenty Four and Paise Eight Only	1572.24
Total Estimated Cost in Figures						**642672.95**
Quoted Amount					**642972.95**	**642673.00**
Quoted Rate in Words		**Rupees Six Lakh Fourty Two Thousand Six Hundred & Seventy**				

Signature of Tenderer with seal