

**KERALA AGRICULTURAL UNIVERSITY**  
**DIRECTORATE OF PHYSICAL PLANT**  
**Quotation Schedule**

**Name of work:-** Providing Partition, ceiling and acoustic in the newly constructed Academic Research Building at M.C Vellanikkara.

Sl. No.	Description	Quantity	Rate		Amount
			Figures	Words	
1	Providing and fixing suspended false ceiling in all floors up to 3.60 m high using departmental materials such as , Uncoloured plain sherah cement fibre board of thickness not less than 6mm ,G.I perimeter channels ,ceiling section, intermediate section , L-angles and fibre cement board fixed to ceiling, brick wall/partition with the help of nylon rawl plugs and screws. Including one coat of primer, two coat of cement putty, and two coat of plastic emulsion to cement fibre board etc complete, materials as per approved design and direction of departmental officers (G.I section and sherah board will be supplied at the site).	590 m <sup>2</sup>			
2	Providing Acoustic work with departmental sherah fibre cement designed plank of 8mm, 150 mm wide fixed at GI frame work using anchor bolt and screw. The inter mediate gap between wall and the frame is filled with filling materials, which has to be covered with acoustic fabric, each plank has to be screwed with Stainless steel flat screws to the frame work as per approved design and direction of departmental officers (G.I section, sherah planks, polyester wadding and fabric materials will be supplied at site).	100 m <sup>2</sup>			
3	Wall panelling with departmental fibre cement designed plank of 8mm thick to the walls as per approved design and direction of departmental officers (sherah planks will be supplied at site).	30m <sup>2</sup>			

Sd/-

**DIRECTOR OF PHYSICAL PLANT (i/c)**