



KERALA AGRICULTURAL UNIVERSITY
Directorate of Physical Plant, KAU- PO-680 656, Thrissur, Kerala

QUOTATION NOTICE No.19/17-18

No.A7/3904/17

Dt: 30/01/18

Sealed competitive quotations are invited from the experienced Firms/Contractors on or before **3.00 P.M.** on **6/2/2018** for executing the following works of "Providing Partition, ceiling and acoustic in the newly constructed Academic Research Building at M.C Vellanikkara."Rate should be quoted in area (m²/sq.ft) basis in the schedule attached separately according to the type of material and conditions below. The quotationer should be experienced in relevant fields and requested to furnish the proof for experience along with the quotation.

Sl. No.	Description	Quantity
1	Providing and fixing suspended false ceiling in all floors up to 3.60 m high using departmental materials such as , Uncoloured plain shera cement fibre board of thickness not less than 6mm ,G.I perimeter channels ,ceiling section, intermediate section , L-angles and fibre cement board fixed to ceiling, brick wall/partition with the help of nylon rawl plugs and screws. Including one coat of primer, two coat of cement putty, and two coat of plastic emulsion to cement fibre board etc complete, materials as per approved design and direction of departmental officers (G.I section and shera board will be supplied at the site).	590 m ²
2	Providing Acoustic work with departmental shera fibre cement designed plank of 8mm, 150 mm wide fixed at GI frame work using anchor bolt and screw. The inter mediate gap between wall and the frame is filled with filling materials, which has to be covered with acoustic fabric, each plank has to be screwed with Stainless steel flat screws to the frame work as per approved design and direction of departmental officers (G.I section, shera planks, polyester wadding and fabric materials will be supplied at site).	100 m ²
3	Wall panelling with departmental fibre cement designed plank of 8mm thick to the walls as per approved design and direction of departmental officers (shera planks will be supplied at site).	30m ²

Conditions:

- 1) Quotationers should have GST Registration and a copy of certificate may be furnished along with the quotation.
- 2) Screws, painting materials and other sundries and all labour required for the work should be supplied by the quotationer.
- 3) Quotationer shall execute an agreement on stamp paper with Rs.200/- within the stipulated period for starting the work. Security Deposit @ 5% of the quoted amount should be deposited while executing the agreement in the form of FDR of Nationalised Bank. This will be released after 3 years or on expiry of one year and executing indemnity bond for the balance period.
- 4) Period of work is within 45 days after executing agreement in stamp paper with RS.200/-. Delay in work will be charged with a fine @ 1% of the contract amount for a period of 3 months.
- 5) The rate should be included all taxes, incidental charges etc. i.e. 5% GST and 1% Workers

Welfare Fund and Income Tax as per rules will be deducted from the bill amount.

- 6) Payment will be made on receipt and verification of bills forwarded to this office after necessary verification by the AE/AEE, ESD Vellanikkara.
- 7) Additional details if any required and the other terms and conditions can be had from the office of the undersigned.

Sd/

DIRECTOR OF PHYSICAL PLANT (i/c)