



KERALA AGRICULTURAL UNIVERSITY
REGIONAL AGRICULTURAL RESEARCH STATION
Mele Pattambi (Post), Palakkad (Dt.), 679 306, Kerala
Email: adrptb@kau.in , rarsptb@kau.in Ph : 0466-2212228

No. D3 – 473/2018

Dated: 10.2.2018

QUOTATION NOTICE

Sealed quotations are invited for erecting an Arch shaped Nursery shed (dismantling/non welded type) with the following specifications in the Station.

Size: 29 x 8 m
15 x 8 m

Arch type structure using GI pipe and cladding with UV stabilized polythene sheet and shade net layer inside. Centre height 5 m and gutter height 3.5 m; Rain water collection using pathy

Foundation: Columns fitted over ground “inserts”/ and bolted to insert pipe.
Specifications of materials: GI pipes 2 mm thick, galvanized B class, with ISI mark, Clamps 3 mm and 2 mm thick, galvanized.
Roofing: 200 micron, UV stabilized 86% light transmission, anti-dust anti drip.
Shade net: 35% Red colour, monofilament – light diffusing 90 gsm
Aluminium profile: Triple spring locking, 0.9 mm thick Zig zag wire – PVC coated spring.

Dimension & requirements	Dia. mm	Nos.	Area
Pillar pipes GI	40		
Structure Arches Pipes GI	32		
Arch Support pipes GI	20		
Pillar Connecting pipes (cross pipes) GI	25		
Purling pipes GI	25		
Lengthwise wind reinforcement Pipes (GI stay)	25		
Gable side wind pipe GI (stay)	25		
Purling pipes for gutter installation GI	32		

6” skirting all around with appropriate foundation using bricks and 2”x2” 10 swg 5” Chain link fencing along the columns all around. Overhead sprinklers with timer for irrigation.

The rate should be inclusive of cost of all materials, labour, unloading and transportation charges and taxes etc. for each structure separately.

Quotation should be accompanied by detailed drawing and specifications

Quotations should reach the undersigned on or before 28.2.2018. The envelope containing the quotations should be super scribed with ‘Nursery shed erection’ and sent to the Associate Director of Research, Regional Agricultural Research Station, Mele Pattambi Post, Palakkad Dist. 679306 (Pin), Kerala State.

Quotations will be opened at 11.30 am on 28.2.2018 in the presence of quotationers present at that time.

Quotation should be accompanied by drawing. Site can be visited on all working days. Quotations received late and those not conforming to specifications will not be accepted. The successful quotationer will have to execute an agreement and remit security deposit of Rs. 5000/- per unit which will be returned after a period of 1 year from the date of completion. The erection of the nursery shed should be completed within 1 month of issue of work order.

The payment in the full will be released immediately on satisfactory completion of the work. All other conditions applicable to purchase and of similar nature in Govt. shall be applicable in this case also.

Sd/-
Associate Director of Research

To: Sri. P S Sajeesh, Junior Programmer – for web hosting in www.rarsptb.kau.in/ Notice Board, Circulation.

//Approved for Issue//


Section Officer